GREAT LAKES NAVIGATION UPDATE


Marie T. Strum, P.E.
U.S. Army Corps of Engineers
Great Lakes Navigation Team
Leader

June 3, 2020 GL Dredging Team

"The views, opinions and findings contained in this report are those of the authors(s) and should not be construed as an official Department of the Army position, policy or decision, unless so designated by other official documentation."














GREAT LAKES NAVIGATION SYSTEM








- Non-linear complex system of interdependent
- Commercial are ports dependent on each other
- 95% of traffic is internal to the Great Lakes
- System saves \$3.9* Billion per year over next least costly mode of transportation
 - * Updating to incorporate latest information on overland rail capacity



GL NAVIGATION FUNDING HISTORY







FY20 GREAT LAKES NAVIGATION PRESIDENT'S BUDGET



PRESIDENT'S BUDGET + WORKPLAN

Great Lakes Navigation Operations & Maintenance

\$88.4M + \$55.8M = \$146.2M

Key O&M Items

\$37.3M in Dredging (18 projects; 2.6M cy) (\$27.8M + \$9.5M)

\$11.4M in Dredged Material Management (\$6M + \$5.4M)

\$16.9M in Soo Locks Maintenance (\$2.6M + \$14.3M)

\$5.9M in Chicago Lock Maintenance

\$2.0M in Black Rock Lock Maintenance

\$20.3M in Navigation Structure Maintenance/Repair

Construction General

\$75.3M + \$50M = \$125.3M New Soo Lock

\$12.3M Indiana Harbor CDF Construction



FY21 GREAT LAKES NAVIGATION PRESIDENT'S BUDGET



Great Lakes Navigation Operations & Maintenance \$104.8M

Key O&M Items

\$37.1M in Dredging (16 projects; 3.1M cy) \$5.9M in Dredged Material Management \$23.5M in Lock Operations & Maintenance \$4.5M for Black Rock Lock Miter Gates

Construction General

\$123.2M New Soo Lock \$16M Calumet CDF Construction







DREDGING










FY20 Dredging Funding and








HISTORICAL FUNDING GREAT LAKES LOW USE PROJECTS (<1M TONS)





President's Budget ■ Workplan/Appropriation






Line

Backlog


Great Lakes Dredging Backlog 1985-2019





Current Dredged Material Placement Methods










SOO LOCK RELIABILITY





MAINTAINING EXISTING SOO LOCKS FACILITY (O&M FUNDED)




O&M - Asset Renewal

 Higher cost component repairs and replacements (Asset Renewal) - \$117.5M thru FY20







FY20 Funded Work

- \$2.6M Poe Lock Gate 1 Repairs
- \$500K Poe Gate Sill Repairs
- \$4.4M Crane Replacement Lock Maintenance
- \$8M Acquisition of Aquadigger to replace Nicolet Strike Removal
- \$2.1M Hydropower Medium Voltage Breaker Replacement Lock Power Supply

Winter Maintenance (Jan-Mar 2020)

- Poe Lock Gate 1 Repairs crack/diagonal repairs
- Poe Lock Gates 1 & 3 Sill Repairs concrete spalling
- Poe Lock Gate 1 Emptying and Filling Valve Repair


FY21 Priorities


- MacArthur Lock Ship Arrestor Repairs
- Asset Renewal Priorities:
 - Poe Lock Gate 1 final phase (repairs & coating replacement)
 - Poe Gate 4 initial phase (crack repairs)
 - Center Dike Rehab (initial phase)



MAINTAINING EXISTING SOO LOCKS FACILITY (CG FUNDED)







WE ARE HERE

Davis and Poe Pumpwells (\$37.3M FY21 Capability)

- The pumpwell system currently services the Poe and Mac lock and will service the New Lock once constructed.
- Design revealed unacceptable safety and construction risk in rehabilitating 100 120 year old wells under operational buildings.
- Due to comparable costs a new well is being constructed instead of rehabilitating existing wells.



PROPOSED NEW SOO LOCK

Existing

Proposed




New lock will have **same dimensions** as existing Poe Lock (1200 ft. length by 110 ft. width and a depth of 32 ft.)




NEW LOCK STATUS






* Early completion could be realized with efficient funding, favorable weather conditions and continuing contracts clause





STREAM CHANNEL DEEPENING





Scope: Deepen upstream approach channel to depth of 30 feet

Construction Status:

Construction awarded 30 January to Trade West Construction Co.


Construction began in late April

Estimated Performance Period: 20 Months

U.S.ARMY

PSTREAM APPROACH WALLS





Scope: Rehabilitate approach walls upstream of New Soo Lock

Design Status: Contract Advertisement in May 2020


Construction Status: Contract award expected in Fall 2020

Estimated Performance Period: 24 Months



NEW LOCK CHAMBER





Scope: Construct new 1,200' long by 110' wide by 32' deep chamber and rehabilitate downstream approach walls

Design Status: In Progress - 70% Design to be complete in June 2020 **Construction Status**: Construction Funding Capability Identified in FY21

(\$102.3M of \$152.3M capability included in the FY21 PBud Request)

Estimated Performance Period: 5-8 Years



OUTREACH



Web Site: www.lre.usace.army.mil/greatlakes/navigation

- Harbor Fact Sheets
- Updated CDF Fact Sheets
- Presentations

Mailing Lists: send information to glnavigation@usace.army.mil

Marie Strum (313) 226-6444 Marie.T.Strum@usace.army.mil



QUESTIONS?



